

# Outagamie County Request for Proposal 2025 Aggregates & Crushed Stone

## Attachment A – Special Provisions

### 1. General

Perform the work under this proposal for the furnishing of Aggregates and Crushed Stone for Outagamie County, Wisconsin. Execute the work as specified in the Standard Specifications for Highway and Structure Construction of the Wisconsin Department of Transportation (Standard Specifications), current edition, the Additional Special Provision 6 (ASP-6), Wisconsin Department of Transportation Construction and Materials Manual (CMM), and these Special Provisions. References to the Department or State in the Standard Specifications shall, in most instances, mean Outagamie County. The term “Engineer” shall mean an authorized representative of the Outagamie County Highway Department. The special provisions in this proposal shall supplement and take precedence over the above-mentioned specifications.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

### 2. Scope of Work

The work under this proposal consists of furnishing fine and coarse aggregates, crushed stone, breaker run, and miscellaneous construction materials and all incidental items necessary to complete the work as included in the proposal.

### 3. Prosecution and Progress

The Department will order materials for construction and maintenance projects on an “as needed” basis in advance of or during the current construction season. The Department reserves the right to receive material outside of the typical construction season, dependent upon weather conditions, availability, budgetary constraints, and other factors.

### 4. General Requirements for Aggregates

#### A General

This special provision describes general requirements for furnishing aggregates from the supplier for pickup by trucks operated or under hire by the Department.

#### B Materials

##### B.1 General

Furnish materials that are produced according to the pertinent requirements of sections 209, 301, 305, 310, 311, 312 and 313 of the Standard Specifications, CMM Section 8 (860) and ASP-6.

##### B.2 Quality Control

Perform Quality Control procedures including sampling, testing, record keeping, etc. according to the applicable sections referenced in B.1.

Perform routine aggregate quality testing for each source proposed for Department use and ensure aggregate quality testing records are maintained on the [WisDOT Approved Products listing](#). The Department reserves the right to reject any aggregate source that does not meet pre-qualification or approval for WisDOT use (i.e. does not appear on the current *WisDOT Approved List of Pits and Quarries*) or does not have a current aggregate quality test on record.

For sources that are not currently listed on the [WisDOT Approved Products listing](#), provide aggregate quality testing documentation to the Department for consideration. A request does not constitute approval.

Submit quality control records to the Department on a daily basis during periods when aggregates are either being produced or loaded out for Department use. Retain all production testing records for aggregates produced for use by the Department for the current construction season for a minimum of three (3) years. Make these production records available to the Department upon request and at no additional cost.

In the event that test records indicate a failing test or aggregate property, cooperatively participate in dispute resolution to determine and resolve deficient properties in a timely manner. The Department reserves the right to issue monetary penalties for properties that are outside of the allowable limits based on the guidelines and methodology of the CMM.

**B.3 Granular Backfill**

Furnish granular and structural backfill materials conforming to sections 209.2 and 210.2 of the Standard Specifications, respectively.

**B.4 Fine Aggregates & Sand**

Furnish fine aggregates conforming to section 501.2.7.2 of the Standard Specifications based on the type of fine aggregates being requested by the Department.

**B.5 Course Aggregates**

Furnish dense-graded and open-graded aggregates conforming to sections 305.2 and 310.2 of the Standard Specifications, respectively, based on the type of aggregates being requested by the Department.

**B.6 Breaker Run**

Furnish breaker run conforming to section 311.2 of the Standard Specifications.

**B.7 Select Crushed Material**

Furnish material conforming to section 312.2 of the Standard Specifications.

**B.8 Seal Coat Aggregate**

Furnish aggregates for seal coating applications conforming to section 475.2 of the Standard Specifications, based on the type of aggregates being requested by the Department, and as modified below.

Seal coat aggregates shall meet the gradations shown below, unless otherwise requested or revised by the Department:

<b>Sieve Size</b>	<b>Percent Passing By Weight (1/4 Inch Aggregate)</b>
3/8 inch (9.5mm)	100
#4 (4.75mm)	0 -17
#8 (2.36mm)	--
#16 (1.19mm)	--
#40 (425mm)	--
#200 (75mm)	0 -1

**B.9 Riprap Stone**

Furnish aggregates for use as riprap conforming to section 606.2.1 of the Standard Specifications.

**C Construction**

The supplier shall provide miscellaneous aggregates and crushed stone materials from the source indicated on the proposal form with appropriate safety and operational features in place.

Submit the Standard Operating Procedures (SOP) for each source when requested by the Department. Submit a current certificate of insurance to the Department in accordance with section 2.0 of the general requirements of this RFP.

**D Measurement**

The Department will measure all aggregate and crushed stone items acceptably furnished by the Ton.

**E Payment**

The Department will pay for measured quantities at the proposal unit price or bid price under the following items.

<u>DESCRIPTION</u>	<u>UNIT</u>
Granular Backfill (Grade)	TON
Structural Backfill (Type)	TON
Sand (Type)	TON
Pit Run	TON
Base Aggregate Dense (size)	TON
Select Crushed Material	TON
Breaker Run	TON
Clear Stone (size)	TON
Seal Coat Aggregate	TON
Buckshot Stone (Pea Gravel)	TON
Waste Screenings	TON
Riprap (size)	TON

Payment for the above items is full compensation for furnishing materials including blasting, crushing, washing, screening, processing, for providing Quality Control documentation, and for all incidental items necessary to complete the work as described in this proposal. The Department will pay for loadout when specified, based on the prices on the proposal form.

The Department will consider adjustments to unit pricing for any proposed unit price that increases or decreases by more than 25%, as long as the cost increase/decrease is shown to be industry-wide. Requests for price adjustments may be initiated by the contractor or the Department with applicable supporting documentation, and shall use the requirements of subsection 104.2.2.4.3 of the standard specification as a basis for considering an adjustment to the contract price.

Proposed unit prices shall remain in effect until March 31, 2026.

**5. Estimated Quantities**

In order to assist in preparation of this proposal, the Department is providing approximate project locations and quantities for the 2025 construction season. Quantities shown are estimates only and the actual purchased quantity may be increased or decreased as necessary to complete individual maintenance and construction project needs. The Department reserves the right to revise the list of projects in any way, including increases or decreases to estimated quantities, or addition

and/or deletion of projects, depending on proposal and/or bid prices received, budgetary restrictions, schedule changes, or other reasons as deemed necessary by the Department.

**Outagamie County Highway Department  
Proposed Projects – 2025 Season**

Project / Limits	Estimated Quantity (TONS)		
	3/4-Inch BAD	1 1/4-Inch BAD	Select Crushed Material
CTH D (STH 76 - Oak Rd)	2,500	---	---
CTH E (CTH N to STH 55)	800	---	---
CTH EE (CTH E - ECL)	1,000	---	---
CTH F (Birch Rd - CTH M)	1,300	---	---
CTH G (Isaar Rd - CTH Y)	800	20,000	6,500
Countywide Maintenance	16,000	6,500	3,500
<b>Project Totals</b>	<b>22,400</b>	<b>26,500</b>	<b>10,000</b>