

Public Involvement Meeting

**County VV
Isaar Road – CTH Y**

**August 17, 2021
Seymour Town Hall**

Agenda

- I. Introductions**
- II. Plan Review**
- III. Traffic**
- IV. Schedule**
- V. Question & Answer (“Open House” format)**

Welcome to the public involvement meeting for the proposed improvements to County VV. The purpose of tonight’s meeting is to familiarize you with the details of the project and to seek your input on the proposed improvements. We encourage you to review the project handout and exhibits on display and direct questions or comments to any of the project representatives. We also encourage you to provide written comments regarding the proposed improvements.

Project Purpose and Need

The purpose of the project is to enhance the safety and quality of County VV within the project limits by improving the roadway surface and pavement structure, widening the shoulder to current standards, and improve the safety of the roadway. The existing asphalt pavement was last improved in 1999.

Project Highlights

The project is located on County VV between Isaar Road and County Y. The proposed project will reclaim and salvage the existing asphalt pavement, lower the existing profile by removing 12-18” of existing road base and subgrade, widen the shoulder width to current standards and match the segment located east of the project limits, and place new asphalt lanes and shoulders. Spot ditching and culvert replacements are also anticipated to improve drainage. New signing and safety improvements will also be incorporated into the project.

Traffic Control

During construction, the project area will be closed to through traffic. A signed detour will be posted, and is anticipated to utilize WIS 55, County G, and County Y. Local access will be maintained for businesses and residents for the duration of the project, including services such as mail delivery and garbage pickup.

Right of Way

Additional highway right-of-way is not anticipated at this time. Small areas of Temporary Limited Easement (TLE) may be necessary for minor slope grading and/or ditching areas, but are anticipated to be minimal.

Proposed Project Schedule

The proposed schedule is as follows:

Final Design	Fall 2021
Utility Relocation (<i>if necessary</i>)	Spring 2022
Construction	Late Summer 2022
Final Paving	Spring/Summer 2023

Public Comments

Attached to this handout is a comment form. We would appreciate any written comments, questions, or concerns you have regarding the proposed project. Please submit comments by August 31, 2021 to highwayemail@outagamie.org, mail them to the above address, or submit them directly to a Highway staff member tonight. You can also use this form to be added to the project's email distribution list, which we use to send periodic updates in regards to the project and to convey updates during construction.

Your comments assist us in developing a project that will serve the needs of the traveling public as well as the needs of the local community. Your input is welcome and appreciated throughout the design process.

For more information or to view information presented at tonight's meeting, please reference the web address: www.outagamie.org/CountyVV
or contact:

Mr. Joe Zellmer, Highway Engineer
Outagamie County Highway Department
1313 Holland Road
Appleton, WI 54911-8947
(920) 832-5673
joseph.zellmer@outagamie.org