Project Information & Facts

T Kaukauna, CTH U
Apple Creek Bridge B-44-0506
CTH U, Outagamie County
Project ID: 6003-00-70

Sponsor Agencies:	Outagamie County / WisDOT Northeast Region
Program:	Federal/State Local Bridge Improvement Assistance Program
Funding:	80% Federal (capped at $2,074,960) for Participating Construction
Project Limits:	Bridge & Approaches (1,038' total project length)
Existing Structure:	Structure No. B-44-0051 Sufficiency Rating = 31.7 (measured on a scale of 0 to 100) Single-Span Steel Girder Bridge constructed in 1960 Clear Roadway Width = 26.0' Overall Length = 112.0'
Existing Approaches:	24' Paved Traveled Way
Traffic Data:	2028 Average Daily Traffic = 2,071 vehicles per day 2048 Average Daily Traffic = 2,261 vehicles per day
Proposed Improvement:	Bridge Replacement with Roadway Approach Improvements New Structure B-44-0506 (Three-Span Concrete Haunched Slab) Clear Roadway Width = 34.0' Overall Length = 120.5'
Proposed Roadway:	24' Wide Paved Traveled Way 6' Shoulders (3' Paved and 3' Unpaved)
Real Estate:	Minor real estate acquisition for additional right-of-way (permanent & temporary) along the east side of County Road U to accommodate grading for the multi-use path and along the west side for grading behind the new beam guard is anticipated.
Preliminary Cost Estimate:	$2,000,000 - $3,000,000
Project Schedule:	Submit Final Construction Docs to WisDOT .... May 1, 2027 Bid Opening ..... August 10, 2027 Construction Timeline ..... Summer 2028 Construction Duration..... approx. 4 months
During Construction:	The bridge will be closed to traffic during construction. A detour route will be posted. Access to adjacent properties will be maintained throughout construction.

Public Input/Comments

Your comments assist us in developing a project that will serve the needs of the traveling public, as well as the needs of the local community. Your input is welcome and appreciated throughout the design process.

There are several ways to submit your feedback by **April 13, 2026:**

1. Fill out the comment form and mail it to Westbrook Associated Engineers, Inc.

2. Email comments or questions to the contact(s) listed below.

For more information, please contact:

Michael Morman
Outagamie County Highway Department
320 South Walnut St.
Appleton, WI 54911
(920) 832-2247
Michael.Morman@outagamie.org

Aaron Palmer, P.E.
Westbrook Associated Engineers, Inc.
P.O. Box 429
Spring Green, WI 53588
(608) 588-7866
apalmer@westbrookeng.com

Public Involvement Meeting Comment Form

T Kaukauna, CTH U
Apple Creek Bridge B-44-0506
CTH U, Outagamie County
Project ID: 6003-00-70

Please mail this form by **April 13, 2026** to the address on the back of this sheet. Comments can also be e-mailed to ***apalmer@westbrookeng.com***. Your comments assist us in developing a project that will serve the needs of the traveling public as well as the needs of the local community. Your input is welcome and appreciated throughout the design process.

Name: _____

Address: _____

Daytime Phone Number (optional): _____

Email Address (optional): _____

Please Print Comments (attach additional sheets if necessary)

_____

_____

_____

_____

_____

_____

_____

_____

_____

_____

_____

_____

_____

_____

_____

The information in this document including names, addresses, phone numbers, e-mail addresses, and signatures is not confidential, and may be subject to disclosure upon request, pursuant to the requirements of the Wisconsin open records law, sections 19.31 - 19.39 of the Wisconsin Statutes.

Fold here

[*Stamp*]

Westbrook Associated Engineers, Inc.
P.O. Box 429
Spring Green, WI 53588
Attn: Aaron Palmer

Fold here to mail